



*City of Springfield
Development and Public Works Department*

*Anticipated Project Schedule
(All dates, times and locations are subject to change.)*

Construction Start: Summer 2013
Construction Completion: Spring 2014

P21067 10th and N Sewer Upgrade – Phase 2

Project Description: This project consists of the placement of 3,250 linear feet of new 24-inch sanitary sewer pipe and 14 new sanitary sewer manholes by open cut method and the placement of 140 linear feet of new 8-inch storm sewer pipe, 120 linear feet of new 15-inch storm sewer pipe, and 10 feet of new 10-inch storm sewer by open-cut method and the removal and replacement of 2 catch basins and 1 storm sewer manhole.



For questions regarding this project you may contact the Project Leader below.

Project Leader: Kyle Greene, Civil Engineer

Phone: 541-726-5750

E-mail: [Kyle Greene](mailto:Kyle.Greene@springfield-or.gov)